

工法比較 数量総括表

道路改良H23その1

区分	工種	種別	細別 / 規格	単位	数量			摘要
					第1工法	第2工法	比較	
工事区分:道路改良								
道路土工								
掘削工								
			掘削(1)土砂 平均運搬距離 L=500m	m3	1,100	1,100		
			掘削(2)土砂 平均運搬距離 L=180m	m3	1,100	1,100		
路体盛土工								
			路体(流用土)	m3	810	1,110	+300	
			路体(流用土) 作業残土	m3	160	170	+10	
			路体(採取土)	m3	0	240	+240	
路床盛土工								
			路床(流用土)	m3	1,200	900	-300	
			路床(採取土)	m3	0	300	+300	
法面整形工								
			法面整形(切土部) レキ質土	m2	270	310	+40	
残土処理工								
			残土処理 平均運搬距離 L=180m	m3	180	190	+10	
法面工								
植生工								
			張芝 野芝(半土付)	m2	270	290	+20	
擁壁工								
作業土工								
			床掘り	m3	560	590	+30	
			基面整正(人力)	m2	260	270	+10	
			埋戻し	m3	340	360	+20	
場所打ち擁壁工(構造物単位)								

工法比較 数量総括表

道路改良H23その1

区分	工種	種別	細別 / 規格	単位	数量			摘要
					第1工法	第2工法	比較	
			もたれ式擁壁 18-8-25(20)	m3	400	460	+60	
			裏込砕石	m3	200	225	+25	
			仮設工					
			工事用道路工					
			工事用道路盛土	m3	500	500		
			工事用道路敷砂利 C40-0 t=20cm	m3	120	120		
			工事用道路補修	式	1	1		